



GRUPPO NAZIONALE DI GEOFISICA  
DELLA TERRA SOLIDA



# Atti del 34<sup>o</sup> Convegno Nazionale

Trieste, 17-19 novembre 2015  
Palazzo dei Congressi  
della Stazione Marittima

**Tema 1: Geodinamica**



ISTITUTO NAZIONALE DI  
OCEANOGRAFIA E DI  
GEOFISICA SPERIMENTALE

GRUPPO NAZIONALE DI GEOFISICA DELLA TERRA SOLIDA



# 34° convegno nazionale

**Trieste**  
17-19 novembre 2015  
Stazione Marittima

ATTI

Tema 1: Geodinamica



ISTITUTO NAZIONALE DI  
OCEANOGRAFIA E DI  
GEOFISICA SPERIMENTALE

## 34° Convegno Nazionale Atti - Tema 1: Geodinamica

---

### Comitato organizzatore

D. Slejko  
D. Albarello  
A. Argnani  
F. Bianco  
G. Caielli  
G. Cassiani  
A. Del Ben  
D. Di Bucci  
M. Dolce  
E. Eva  
G. Florio  
P. Galli  
L. Martelli  
P. Mazzucchelli  
G. Naso  
R. Nicolich  
F. Pacor  
R. Petrini  
L. Sambuelli

A cura di: D. Slejko, A. Riggio,  
A. Rebez, A. Argnani, F. Bianco,  
A. Del Ben, E. Eva,  
P. Galli, R. Petrini

Con la collaborazione di:  
M. Bobbio e P. Giurco

Copertina: M. Sedmach

Impaginazione e stampa:  
Luglioprint, Trieste

Finito di stampare nel mese di novembre 2015

ISBN: 978-88-940442-5-6 questo volume  
ISBN: 978-88-940442-4-9 collezione completa

# Indice

<b>Lectio Magistralis</b> .....	XI
IL TERREMOTO DEL FRIULI: CONSIDERAZIONI SU UN EVENTO SINGOLARE M. Ruscetti .....	XIII
<b>Tema 1 - Geodinamica</b> .....	1
<b>sessione 1.1 - Geologia dei terremoti e sismicità</b> .....	3
COULOMB FAILURE STRESS TRANSFER AND FAULT INTERACTION AT ETNA VOLCANO: SOME CASE-HISTORIES IN THE TIMPE FAULT SYSTEM R. Azzaro, V. Maiolino, M. Palano .....	5
ANALYZING SEISMOINDUCED EFFECTS AND FRAGILE DEFORMATION IN THE AVOLA VECCHIA AREA (SOUTHERN SICILY): IMPLICATION FOR ACTIVE TECTONICS AND SEISMICITY M.S. Barbano, C. Pirrotta, G. De Guidi, C. Farina .....	11
FEASIBILITY STUDY OF A NETWORK FOR THE MICROSEISMIC MONITORING OF THE NATURAL GAS FIELD OF "SANT'ALBERTO" (PO PLAIN, ITALY) S. Carannante, E. D'Alema, M. Buttinelli, M. Anselmi, S. Lovati, M. Massa, P. Augliera, G. Franceschina .....	17
THE ORIGIN OF THE ACTIVE CRUSTAL STRETCHING AT THE SOUTHERN EDGE OF THE CALABRIA ARC S. Catalano, F. Pavano, G. Romagnoli, G. Tortorici .....	26
GRAVIQUAKES AND ELASTOQUAKES C. Doglioni, E. Carminati, P. Petricca, F. Riguzzi .....	32
LOST EARTHQUAKES BETWEEN ANTIQUITY AND MIDDLE AGE. ARCHEOLOGICAL INDICATION FROM VOLCEI (SOUTHERN APENNINE) P. Galli, A. Lagi .....	39
LATE PLEISTOCENE REVERSE SURFACE FAULTING AT THE PECETTO DI VALENZA SITE (AL - NORTHERN ITALY): PRELIMINARY RESULTS F. Livio, M.F. Ferrario, C. Frigerio, A.M. Michetti, A. Zerboni, L. Bonadeo, G. Fioraso, A. Irace, F. Brunamonte .....	45
INTENSITY-BASED SOURCE INVERSIONS OF THE M8 EARTHQUAKES OF BIHAR-NEPAL (1934) AND OF ASSAM (1897); FAST KF SCENARIO OF THE M7.8 GORKHA, 2015 EARTHQUAKE F. Pettenati, L. Sirovich, D. Sandron .....	50
SUBMARINE EARTHQUAKE GEOLOGY AS A TOOL FOR SEISMIC HAZARD ASSESSMENT IN THE CALABRIAN ARC A. Polonia, S. Romano, L. Gasperini, S.C. Vaiani, G. Gasparotto, E. Colizza, L. Torelli .....	57
<b>sessione 1.2 - Processi tettonici attivi: osservazioni e modelli interpretativi</b> .....	65
LOCAL EARTHQUAKE TOMOGRAPHY IN THE JUNCTION BETWEEN SOUTH-EASTERN ALPS AND EXTERNAL DINARIDES USING THE SEISMIC DATA OF THE CE3RN NETWORK L. Colavitti, L. Tiberi, G. Böhm, G. Costa, A. Gallo .....	67
MAPPATURA DELL'ANTICLINALE DI MIRANDOLA, ITALIA, MEDIANTE MISURE HVSR G. Tarabusi, R. Caputo .....	75

GEOGUARD: UN NUOVO SERVIZIO DI MONITORAGGIO GEODETICO PER L'OSSERVAZIONE DI SEGNALI GEODINAMICI S. Caldera, E. Realini, M. Reguzzoni, D. Sampietro, F. Sansò . . . . .	83
DATA BASE OF ITALIAN VELOCITIES AND STRAIN RATES AT PERMANENT GNSS SITES A. Caporali, M. Bertocco, J. Zurutuza . . . . .	89
THE GPS VERTICAL KINEMATIC PATTERN IN THE ITALIAN PENINSULA: CHARACTERISTICS AND ANTHROPOGENIC – GEODYNAMIC IMPLICATIONS N. Cenni, P. Baldi, M.E. Belardinelli, S. Gandolfi, F. Loddo, E. Mantovani, M. Viti . . . . .	96
COMPLEX GEOMETRIES IN THE PLIO-QUATERNARY SEQUENCE IN THE WEST SARDINIAN MARGIN G. Guion, A. Del Ben, A. Mocnik, R. Geletti . . . . .	102
ANALYSIS OF GEOLOGICAL, SEISMOLOGICAL AND GRAVIMETRIC DATA FOR THE IDENTIFICATION OF ACTIVE FAULTS IN ABRUZZO AREA (CENTRAL ITALY) P. Luiso, V. Paoletti, G. Gaudiosi, R. Nappi, F. Cella, M. Fedi . . . . .	107
A GEOPHYSICAL TRANSECT ACROSS THE CENTRAL SECTOR OF THE FERRARA ARC: PASSIVE SEISMIC INVESTIGATIONS – PART II A. Mantovani, N. Abu Zeid, S. Bignardi, G. Santarato . . . . .	114
MAIN TECTONIC IMPLICATIONS OF THE ONGOING KINEMATIC PATTERN (GPS) IN THE ITALIAN REGION E. Mantovani, N. Cenni, M.Viti, D. Babbucci, C.Tamburelli . . . . .	120
A GEOPHYSICAL TRANSECT ACROSS THE CENTRAL SECTOR OF THE FERRARA ARC: DETAILED GRAVIMETRIC SURVEY – PART I F. Palmieri, A. Mantovani, G. Santarato. . . . .	127
RECENT/PRESENT DEFORMATION PATTERN IN THE NORTHERN APENNINES M. Viti, E. Mantovani, D. Babbucci, C. Tamburelli, N. Cenni, M. Baglione, V. D'Intinosante . . . . .	133
<b>sessione 1.3 - Vulcani e campi geotermici . . . . .</b>	<b>141</b>
PRELIMINARY MICROTREMOR SURVEY RESULTS IN SALINELLE MUD VOLCANOES: PATERNÒ, ITALY F. Panzera, S. Sicali, G. Lombardo, S. Imposa . . . . .	143
EVALUATION OF THE EFFECTS INDUCED ON GROUNDWATER'S THERMAL STATE AFTER RE-INJECTION OF ALTERED TEMPERATURE WATER: THE CASE STUDY OF HEAT TRANSPORT SIMULATION IN THE SHALLOW AQUIFER OF TURIN CITY (NW ITALY) D. Barbero, D.A. De Luca, M.G. Forno, M. Lasagna, A.Tissoni, M. Zagami . . . . .	150
FEASIBILITY OF HIGH-FREQUENCY MICRO-GASCHROMATOGRAPHY SOIL GAS MONITORING REVEALED AT LA SOLFATARA (CAMPI FLEGREI, ITALY) S. Sicola, M.L. Carapezza, M. Ranaldi, F. Sortino, L. Tarchini . . . . .	158
INSIGHTS INTO THE SEISMICITY AND ERUPTIONS OF PANTELLERIA ISLAND AND ITS SURROUNDINGS (SICILY CHANNEL, ITALY) S. Spampinato, A. Ursino, M.S. Barbano, C. Pirrotta, S. Rapisarda, G. Larocca, P.R. Platania . . . . .	163
MAGMA DEGASSING, HEATING AND DEFORMATION AT CAMPI FLEGREI CALDERA G. Chiodini, F. Quarenì, S. Caliro, C. Cardellini, A.R. Mangiacapra, Z. Petrillo . . . . .	170

- Pizzi A., Galadini F.; 2009: *Pre-existing cross-structures and active fault segmentation in the northern-central Apennines*. *Tectonophysics*, **476**, 304-319. doi: 10.1016/j.tecto.2009.03.018.
- Rovida A., Camassi R., Gasperini P., Stucchi M. (eds.); 2011: CPTI11, the 2011 version of the Parametric Catalogue of Italian Earthquakes. Milano, Bologna - <http://emidius.mi.ingv.it/CPTI>, DOI:10.6092/INGV.IT-CPTI11.
- Royden L. H., Patacca E., Scandone P.; 1987: *Segmentation and configuration of subducted lithosphere in Italy: An important control on thrust-belt and foredeep- basin evolution* - *Geology*, **15**, 714 – 717.
- Vezzani L., Ghisetti F.; 1998: *Carta geologica dell'Abruzzo, 1:100000*, SELCA, Via R. Giuliani, Firenze.

## A GEOPHYSICAL TRANSECT ACROSS THE CENTRAL SECTOR OF THE FERRARA ARC: PASSIVE SEISMIC INVESTIGATIONS – PART II

A. Mantovani, N. Abu Zeid, S. Bignardi, G. Santarato

*Dipartimento di Fisica e Scienze della Terra, Università degli Studi di Ferrara, Italy*

**Introduction.** The architecture of the Po Plain foredeep filling, from Pleistocene onward, is characterized by a generally “regressive” trend, interrupted by lesser fluctuations, evidenced by the transition from offshore Pliocene deposits to marine-marginal and then to alluvial Quaternary sediments (Ricci Lucchi, 1986; Amorosi and Colalongo, 2005; Amorosi, 2008).

The great number of subsurface data collected during hydrocarbon explorations and water research (AGIP Mineraria, 1959; Aquater, 1976, 1978; Aquater-ENEL, 1981; Pieri and Groppi, 1975, 1981; RER & ENI-AGIP, 1998; Boccaletti *et al.*, 2004, 2011; Ferrara province - RER 2007) allowed to map the main quaternary unconformities: the most recent surface, at regional scale, is the base of the Upper Emiliano-Romagnolo Synthem (AES; Boccaletti *et al.*, 2004) which is made up of a series of different depositional cycles whose limits are placed in correspondence of the bottom of the “transgressive” marine deposits. The ‘transgressive’ portion of each cycle is characterized by the presence of fine materials (*e.g.* floodplain, marsh and coastal plain clays) with subordinated sandy intercalations. Instead, the ‘regressive’ sequence consists of alluvial plain deposits (*e.g.* fine sediments of overflowing river) where channel sands are subordinated in the form of isolated lenticular bodies. On the top of each cycle, the channel sands become abundant, thus forming laterally wider bodies (RER & ENI-AGIP, 1998; ISPRA, 2009).

The studies conducted by the Regione Emilia-Romagna & ENI-AGIP (1998), Boccaletti *et al.* (2004, 2011), Abu Zeid *et al.* (2014) and Ferrara province - RER (2007) revealed that the Quaternary succession is highly deformed and confirmed that the transitions between marine-continental sediments are the result of important tectonic phases followed by periods of strong subsidence. Therefore, the strong variable thickness of the Quaternary sequence from several hundreds to few tens of meters in correspondence of the growing anticlines; *i.e.* Mirandola, Casaglia, Argenta reflects the influence of the complex evolution of the blind thrusts belonging to the Ferrara Arc.

Previous geophysical studies conducted by numerous authors (*e.g.* Priolo *et al.*, 2012; Paolucci *et al.*, 2015) focused the attention on mapping the fundamental resonance frequencies and the corresponding shear-wave velocity profiles in the area affected by the Emilia 2012 seismic sequence by independently interpret the HVSR curves (in the first case) or using a simplified power law to describe  $V_s$  variation with depth in the latter case. This way, they were able to establish a link between the two main resonance peaks to known subsurface geological contacts. However, no information on possible lateral variations could be deduced from such interpretation.

With this premise, we carried out a geophysical survey along a profile, ca. 27-km long and oriented SSW-NNE, almost perpendicular to the regional trend of the buried structures belonging






Fig. 1 – a) Simplified tectonic map of the blind northern Apennines showing the studied area [black boxes ESE of Ferrara: modified from CNR-PFG (1991)]. b) Location of the measured sites (blue dots) along investigated profile (black line).

to the central sector of the Ferrara Arc (Fig. 1a), which is one of the three arcs consisting of blind, north-verging thrusts and folds that represent the external northern Apennines front (Pieri and Groppi, 1981; Bigi *et al.*, 1982; Boccaletti *et al.*, 2004). The investigated profile runs in the middle of the elongated area investigated by the detailed gravimetric survey, described in the companion paper (see Palmieri *et al.*, 2015), between Traghetti (near Molinella) and Formignana (Fig. 1b).

Because the density variations of the Late Quaternary deposits are negligible, even performing a much denser grid of gravity measurements, the resolution of this approach, as described in the above mentioned companion paper, would not be sufficient to detect and reconstruct the surfaces and geometries of bodies in the shallow subsurface. In addition, the geometry of the sedimentary bodies, accumulated in the alluvial plain, is generally characterized by sharp lateral variations and hence the interfaces commonly lack planar geometry showing curvatures with wavelength varying between one to ten hundred meters and several meters wide. Accordingly, as far as the expected deformation structures (*i.e.* fault-propagation folds) in the youngest and hence shallowest deposits could have comparable dimensions, the gravimetric survey was integrated by geophysical measurements sensitive to more variable properties in the shallowest subsurface than density.

Therefore, our investigations based on seismic techniques, exploited the ambient seismic noise. In particular, we applied the ESAC (Aki, 1957, 1964; Asten and Henstridge, 1984; Otori *et al.*, 2002) strategy to obtain several 1D shear wave velocity profiles, providing quantitative shear velocity models down to 120-150 m depth, and HVSR technique (Nakamura, 1989) to infer the fundamental resonance frequency and an estimate of the depth of major impedance contrast(s) at each site. Afterwards, the local 1D Vs profiles and HVSR curves were assembled in order to reconstruct two independent pseudo-2D sections. In what follow we shall show that it is possible to obtain reliable pseudo-2D sections from surface seismic noise data so emphasizing the occurrence of lateral shear wave velocity and spectral ratio amplitude variations. Further, a characterization beyond the nominal depth of 30m results in very useful information for site characterization especially for the quantitative evaluation of the local site specific seismic response (Abu Zeid *et al.*, 2012).

**Data acquisition.** Along the investigated profile, we carried out 26 ESAC arrays associated with single station recordings at the centre of the array, roughly one kilometre spaced. The coordinates of the investigated sites are listed in Tab. 1.

Tab. 1 - Coordinates (WGS84 – UTM, zone 32N) of the seismic noise measurements.

site	type of measurement	latitude (UTM 32N)	longitude (UTM 32N)	site	type of measurement	latitude (UTM 32N)	longitude (UTM 32N)
01	array	4946530	714459	14	array	4958360	719532
01	single station	4946550	714380	14	single station	4958390	719530
02	array	4947330	715029	15	array	4959510	720312
02	single station	4947320	715028	15	single station	4959540	720302
03	array	4948470	715036	16	array	4960300	720546
03	single station	4948450	715037	16	single station	4960290	720563
04	array	4949020	715811	17	array	4961180	720964
04	single station	4949020	715802	17	single station	4961190	720981
05	array	4950090	716382	18	array	4962270	721064
05	single station	4950110	716382	18	single station	4962290	721059
06	array	4950990	716572	19	array	4963050	721965
06	single station	4950990	716573	19	single station	4963050	721951
07	array	4951940	716901	20	array	4963680	722199
07	single station	4951930	716899	20	single station	4963670	722225
08	array	4952830	717258	21	array	4964950	722408
08	single station	4952840	717285	21	single station	4964950	722387
09	array	4953800	717964	22	array	4965510	722620
09	single station	4953790	717965	22	single station	4965530	722599
10	array	4954610	718249	23	array	4966490	723283
10	single station	4954610	718264	23	single station	4966480	723278
11	array	4955510	718460	24	array	4967340	723543
11	single station	4955530	718455	24	single station	4967330	723553
12	array	4956410	718774	25	array	4968020	723757
12	single station	4956430	718772	25	single station	4968010	723763
13	array	4957680	719364	26	array	4969380	724651
13	single station	4957670	719364	26	single station	4969390	724638

The ESAC (Extended Spatial Auto-Correlation; Aki, 1957, 1964; Asten and Henstridge, 1984, Ohori *et al.*, 2002) consists of collecting the ambient seismic noise by means of an array (seismic antenna) employing vertical geophones, laid out in an L, T or X geometry, allowing for different length of the segments in order to fit the available space at the measurement site, especially when in urban areas. Data are Fourier transformed and combined keeping into account the shape of the antenna to obtain the dispersion pattern of the Rayleigh waves. Then, an inversion process allows estimating the local vertical sequence of shear wave velocity ( $V_s$ ), assuming a 1-D subsurface model. In the present survey, L-shaped arrays, composed of 24 geophones, 8 m spaced, were laid out at each site. We used 3-components 4.5 Hz proper frequency geophones. Seismic noise was recorded separately both for the vertical and horizontal components, obtaining time series of 15 minutes long sampled at 500 Hz. The inversion of the dispersion curves afterwards allowed for the 1-D shear wave velocity estimation using a set of constant thickness layers. Phase velocity data inversion was accomplished using a






Fig. 2 – Pseudo-2D shear-wave velocity section reconstructed by the interpolation of several 1D shear-wave models obtained from the inversion of the ESAC seismic noise data.

“minimum roughness regularization” strategy, so to obtain smooth transitions with depth but still maintaining the capability of capturing the major impedance contrasts.

The HVSR (Horizontal-to-Vertical Spectral Ratio) technique, first proposed in 1970 by Nogoshi and Igarashi, based on the initial study of Kanai and Tanaka (1961), and today popular thanks to Nakamura (1989), is a “passive” method, which uses three-component recordings of ambient seismic noise to evaluate the site fundamental resonance frequency(ies), by estimating the horizontal-to-vertical ratio of the spectral amplitudes of motion. The measurements of the seismic noise were performed using a 3-component short-period seismometer ( $f_c = 2$  Hz) for time intervals variable between 30 and 50 minutes. The final HVSR curves as a function of frequency are given by the average of the H/V ratio computed for each window (window size = 60 s). The curves were computed by averaging the horizontal spectra with the quadratic average and dividing it for the vertical spectrum. Such spectra were smoothed following the filter proposed by Konno and Omachi (1986) using a constant b value of 40. Moreover, seismic noise source directionality was evaluated for all the measurements.

**Results: pseudo-2D sections.** The discrete information of all 1D models was interpolated with a minimum curvature algorithm in order to obtain the pseudo-2D velocity section. The resulting  $V_s$  profile is shown in Fig. 2. Although 1D models locally reached higher depths, the section we show reports the distribution of  $V_s$  down to an average depth of about 160 m b.g.l. (considering that the elevation of the sites ranges between 0 and 4.5 m a.s.l.). The shear wave velocity ranges between 100-150 m/s, just below ground surface, and locally reaches 600 m/s at the maximum investigation depths. The vertical gradient of  $V_s$  is stronger between sites 03-13 and between sites 21-26, while in the southernmost and central portions of the profile, between sites 01-02 and 14-20 the gradient is weaker and the  $V_s$  at 160 m b.s.l. is ca. 400-450 m/s. If we compare the  $V_s$  profile with the Structural Model of Italy (Bigi *et al.*, 1992) we observe that the strongest  $V_s$  gradients are located above the sets of thrust faults respectively pertaining to the Argenta and Ferrara anticlines; conversely, the sites where the gradient is weaker are located above a tectonically “depressed” area bounded by a reverse fault to the north.

The corresponding frequency section, obtained using the HVSRprofile routine (Herak *et al.*, 2010), which performs a side-by-side assembly of the observed HVSR-spectra, is based on the 26 single station measurements of seismic noise, elaborated following the HVSR method. Considering the characteristics of the seismometer and the influence of weather-climate conditions for frequencies below 0.5 Hz (SESAME, 2004), the analysis was limited to the frequency band between 0.5 and 5 Hz. The HVSR amplitudes, depending on the impedance contrast at the discontinuity surface, are color-coded and these are greater in the southern portion of the profile with respect to the northern one. The fundamental frequency varies along the profile from a minimum of 0.55 Hz up to a maximum of 1.6 Hz (Fig. 3a).

Assuming the  $V_s$  pattern and the fundamental resonance frequency variations to be determined by lateral lithological variations, especially in terms of differential compaction (i.e. age) of the sediments, the two pseudo-2D sections (Figs. 2, 3a) allow hypothesizing the




Fig. 3 – a) Smoothed HVSR profile obtained by gridding each average HVSR curve, between 0.5 and 5 Hz. Relative amplitudes are color-coded (see colorbar). The HVSR spectra of each measurement, which were grouped together according to a comparable fundamental resonance frequency, are also shown. b) Result of the HVSR curve inversion of site n. 6 with the “OpenHVSR” routine. On the left graph are shown the observed HVSR spectra (black line) and the best curve obtained after the inversion procedure (red line). On the left diagram are shown the Vs starting model from ESAC survey (blue line) and the final Vs profile relative to the best HVSR curve (red line). c) Result of the HVSR curve inversion of site n. 14.

occurrence of buried anticline structures in correspondence to the “condensed” stratigraphy and their recent tectonic evolution. This is further confirmed by a preliminary inversion of some ad-hoc selected HVSR curves, performed using the open source “OpenHVSR” routine, developed by our research group to specifically invert large HVSR datasets; which shall be freely available soon. In Figs. 3b and 3c the obtained results of two HVSR curves are shown. The smooth Vs subsurface model obtained from the ESAC was used as starting model for the HVSR inversion. This allowed to start from a model already in the basin attraction of the HVSR inversion global minima. We were so able to optimize the local Vs profiles to both minimize the ESAC and the HVSR objective functions even if the two inversion routines are based on different assumptions.

Despite these limitations,, the resultant depth of the major impedance contrast is consistent with those of the other geophysical tests and available information about the subsurface stratigraphy. The comparison with the available stratigraphic data (RER & ENI-AGIP, 1998; Ferrara province – RER, 2007; Martelli *et al.*, 2014) indicates a good correspondence with the known main stratigraphic unconformities. In particular, the seismic pseudo-bedrock here detected could correspond to the contact between two Middle Pleistocene sedimentary cycles, both belonging to higher rank sedimentary cycle represented by the Upper Emiliano-Romagnolo Synthem (AES).

**Conclusions and future works.** The reconstructed pseudo-2D sections document the possibility to highlight the recent tectonic activity of buried structures underlying the eastern sector of the Po Plain by means of low-cost geophysical surveys (not expensive equipment nor large teams). The seismic passive methods allowed collecting a massive dataset in a short period of time, which in turn, allowed retrieving a large number of local 1D shear wave velocity

profiles that were capable of exploring the subsurface down to ca. 150-200 m depth. Further, the fundamental resonance frequencies and the depth to the major impedance contrast of the investigated sites were obtained. Accordingly, it is possible to carry out a sufficient number of such measurements in order to derive reliable pseudo-2D sections, several kilometers-long, so emphasizing the possible occurrence of lateral shear wave velocity (and amplitude) variations, which will likely reflect the stratigraphic changes.

Although we did not observe in the reconstructed  $V_s$  pseudo-2D section the velocity values that should be expected for a strict definition of the position of the seismic bedrock (i.e.  $V_s \geq 800$  m/s), it is however possible to recognize a pseudo-bedrock located roughly at 100-150 m depth and characterized by  $V_s$  values between 400 and 500 m/s. As a benefit result, the subsurface characterization beyond the traditional 30 m represents a very useful information toward a better urban planning and to a more realistic evaluation of the local site response, especially in view of anticipating new laws that may in the future prescribe to extend this kind of investigations to higher depths.

The comparison between the results described and discussed above with those of the companion paper (see Palmieri *et al.*, 2015), suggests that the shallow stratigraphic features documented in this work can be directly associated with the deep ongoing tectonic activity of the blind thrusts throughout the Quaternary.

**Acknowledgements.** This study has benefited from funding provided by the Italian Presidenza del Consiglio dei Ministri - Dipartimento di Protezione Civile (DPC). This paper does not necessarily represent the official opinion and policies of the DPC.

## References

- Abu Zeid, N., Bignardi, S., Caputo, R., Mantovani, A., Tarabusi, G., Santarato, G.; 2014: *Shear-wave velocity profiles across the Ferrara arc: a contribution for assessing the recent activity of blind tectonic structures*. Proceedings of the 33th National Convention National Group Solid Earth Geophysics. ISBN 978-88-940442-2-5.
- Abu Zeid, N., S. Bignardi, S., Caputo, R., Santarato, G., Stefani, M.; 2012: *Electrical Resistivity Tomography investigation on co-seismic liquefaction and fracturing at San Carlo, Ferrara Province, Italy*. Annals of Geophysics. Vol. 55; p. 713-716, ISSN: 2037-416X, DOI: 10.4401/ag-6149.
- AGIP MINERARIA; 1959: *Campi gassiferi padani*. Atti Convegno Giacimenti Gassiferi dell'Europa Occidentale. Acc. Naz. Lincei, 2, pp. 45-497.
- Aki, K.; 1957: *Space and time spectra of stationary stochastic waves, with special reference to microtremors*, Bull. Earthquake Res. Inst. 35, 415-456.
- Aki, K.; 1964: *A note on the use of microseisms in determining the shallow structures of the earth's crust*, Geophysics 29, 665-666.
- Amorosi, A.; 2008: *Delineating aquifer geometry within a sequence stratigraphic framework: evidence from the Quaternary of the Po River Basin, Northern Italy*. In: Amorosi, A., Haq, B.U., Sabato, L. (Eds.), *Advances in Application of Sequence Stratigraphy in Italy*, vol. 1. GeoActa Special Publication, pp. 1-14.
- Amorosi A. and Colalongo M.L.; 2005: *The linkage between alluvial and coeval nearshore marine successions: evidence from the Late Quaternary record of the Po River Plain, Italy*. In: Blum, M.D., Marriott, S.B., Leclair, S.F. (Eds.), *Fluvial Sedimentology VII*, vol. 35. Special Publication of the International Association of Sedimentologists, pp. 257-275.
- AQUATER; 1976: *Elaborazione dei dati geofisici relativi alla Dorsale Ferrarese*. Rapporto inedito per ENEL.
- AQUATER; 1978: *Interpretazione dei dati geofisici delle strutture plioceniche e Quaternarie della Pianura Padana e Veneta*. Rapporto inedito per ENEL.
- AQUATER-ENEL; 1981: *Elementi di neotettonica del territorio italiano*. Volume speciale, Roma.
- Asten, M. W., and Henstridge J. D. (1984): *Array estimators and the use of microseisms for reconnaissance of sedimentary basins*, Geophysics 49, 1828-1837.
- Bigi G., Cosentino D., Parotto M., Sartori R., and Scandone P.; 1992: *Structural Model of Italy, scale 1:500.000*. Prog. Fin. Geodinamica, Quad. "La Ricerca Scientifica", C.N.R., 114 (3), Roma.
- Boccaletti M., Bonini M., Corti M., Gasperini G.P., Martelli L., Piccardi L., Severi P., Vannucci G.; 2004: *Carta sismotettonica della Regione Emilia-Romagna scala 1:250000*. Note illustrative, A cura di M. Boccaletti e L. Martelli. S.EL.C.A, Firenze, 2004.
- Boccaletti M., Corti G. and Martelli, L.; 2011: *Recent and active tectonics of the external zone of the Northern Apennines (Italy)*. Int. J. Earth Sci. (Geologische Rundschau), 100:1331-1348.
- Ferrara province - RER; 2007: *Risorse idriche sotterranee della Provincia di Ferrara*. Provincia di Ferrara, Servizio



- Politiche della Sostenibilità e Cooperazione Internazionale; Regione Emilia-Romagna, Servizio Geologico, Sismico e dei Suoli; Università degli Studi di Ferrara, Dipartimento di Scienze della Terra, DB Map, Firenze, Italy, 80 pp.
- Herak M., Allegretti I., Herak D., Kuk K., Kuk V., Maric, K., Markusic, S. and Stipcevic, J.; 2010: *HVSR of ambient noise in Ston (Croatia): comparison with theoretical spectra and with the damage distribution after the 1996 Ston-Slano earthquake*, B. Earthq. Eng., 8, 483–499.
- Holbrook J. and Schumm S.A.; 1999: *Geomorphic and sedimentary response of rivers to tectonic deformation: a brief review and critique of a tool for recognizing subtle epeirogenic deformation in modern and ancient settings*, Tectonophysics, 305, 287-306.
- ISPRA; 2009: *Carta Geologica d'Italia, Foglio 204 Portomaggiore*. Coord. Scientifico: Calabrese et al., Regione Emilia-Romagna. ISPRA, Servizio Geologico d'Italia – Regione Emilia-Romagna, Servizio geologico, sismico e dei suoli. SystemCart, Roma.
- Kanai K. and Tanaka T.; 1961: *On microtremors*, VIII Bull. Earthq. Res. Inst. 39.
- Martelli L., Severi P., Biavati G., Rosselli S., Camassi R., Ercolani E., Marcellini A., Tento A., Gerosa D., Albarello D., Guerrini F., Lunedei E., Pileggi D., Pergalani F., Compagnoni M., Fioravante V., Giretti D.; 2014: *Analysis of the local seismic hazard for the stability tests of the main bank of the Po river (Northern Italy)*. Boll. Geofis. Teor. Appl., 55, 119-134.
- Nakamura Y.; 1989: *A Method for Dynamic Characteristics Estimation of Subsurface using Microtremor on the Ground Surface*, Quarterly Report of Railway Technical Research Institute (RTRI), Vol. 30, No.1.
- Nogoshi M. and Igarashi T.; 1970: *On the propagation characteristics of microtremors*. J. Seism. Soc. Japan 23, 264-280.
- Ohori M., Nobata A., Wakamatsu K.; 2002: *A Comparison of ESAC and FK Methods of Estimating Phase Velocity Using Arbitrarily Shaped Microtremor Arrays*. BSSA, 92, 2323–2332.
- Okada Y.; 1985: *Surface deformation due to shear and tensile faults in a half-space*. Bull. Seism. Soc. Am., 75, 1135-1154.
- Okada, H., K. Matsushima and E. Hidaka; 1987: *Comparison of spatial autocorrelation method and frequency wavenumber spectral method of estimating the phase velocity of Rayleigh waves in long-period microtremors*, Geophys. B. Hokkaido Univ. 49, 53-62 (in Japanese with English abstract).
- Pieri M. & Groppi G.; 1975: *The structure of the Pliocene-Quaternary sequence in the subsurface of the Po and Veneto Plains, the pedepenninic Basin and the Adriatic Sea*. Quad. Ric. Scient., 90, pp. 409-415.
- Pieri M. & Groppi G.; 1981: *Subsurface geological structure of the Po Plain, Italy*. CNR, Prog. Final. Geodinamica, pubbl. n. 414, Napoli.
- Priolo E., M. Romanelli, C. Barnaba, M. Mucciarelli, G. Laurenzano, L. Dall'Olio, N. Abu-Zeid, R. Caputo, G. Santarato, L. Vignola, C. Lizza and P. Di Bartolomeo; 2012: *The Ferrara Thrust Earthquakes of May-June 2012 – Preliminary Site Response Analysis at the Sites of the OGS Temporary Network*. Annals of Geophysics, 55 (4), 7 pp.
- RER & ENI-AGIP; 1998: *Riserve idriche sotterranee della Regione Emilia-Romagna*. A cura di G. DI DIO. S.EL. CA. (Firenze).
- Ricci Lucchi F.; 1986: *Oligocene to Recent foreland basins of northern Apennines*. In: PH. Allen and P. Homewood (Eds.), Foreland Basins, IAS Special Publication No. 8, 105-139.
- Site Effects Assessment using Ambient Excitations (SESAME) European project, 2004; Deliverable D23.12: *Guidelines for the implementation of the H/V spectral ratio technique on ambient vibrations: measurements, processing and interpretation*; deliverable D13.08, Final report WP08, Nature of noise wavefield.
- Schumm S.A., Dumont J.F and Holbrook J.M.; 2000: *Active Tectonics and Alluvial Rivers* (Cambridge University Press), pp. 290.

## MAIN TECTONIC IMPLICATIONS OF THE ONGOING KINEMATIC PATTERN (GPS) IN THE ITALIAN REGION

E. Mantovani<sup>1</sup>, N. Cenni<sup>2</sup>, M. Viti<sup>1</sup>, D. Babbucci<sup>1</sup>, C. Tamburelli<sup>1</sup>

<sup>1</sup> Dipartimento di Scienze Fisiche, della Terra e dell'Ambiente, Università di Siena, Italy

<sup>2</sup> Dipartimento di Fisica ed Astronomia, Università di Bologna, Italy

**Introduction.** The geodynamic context in the Mediterranean region is still object of debate. Some authors (e.g., Mantovani *et al.*, 2006, 2007, 2009; Viti *et al.*, 2006, 2011) suggest that the convergence of the confining plates (Africa, Eurasia and the Anatolian-Aegean system)